Calder & Finch Surveyors
Chartered Building Surveyors

7 Gresham Court, Ashbourne Road, Eastbury EB2 4TL
Telephone 01234 000111 · surveys@calderfinch.example

14 May 2026

Mr R. Whitcombe
18 Orchard Row
Eastbury EB1 9QP

Our ref: CF/2026/0457

Structural Survey Summary: 18 Orchard Row

Dear Mr Whitcombe,

Thank you for instructing us to inspect the above property on 28 April 2026. This letter summarises our main findings. The full report is enclosed and should be read alongside this summary.

Summary of findings

The house is in fair condition for its age, and we found no sign of serious structural movement. The table lists each element that needs attention, with our suggested action and its priority.

Element	Condition	Action	Priority
Roof covering	Fair; some slipped tiles	Repair within 12 months	Medium
Chimney stack	Cracked pointing	Repoint before autumn	High
Timber windows	Rot to two sills	Replace the sills	Medium
Drainage	Gully partly blocked	Clear and test	Low
Electrics	Installation not tested	Obtain an inspection	High
Damp	No rising damp found	None required	None
Gutters	Leaking at two joints	Re-seal the joints	Low

Recommendations

1. Arrange for the chimney stack to be repointed before the autumn.
2. Obtain quotations for the following:
   (a) replacement of the two window sills;
   (b) re-sealing of the gutter joints.
3. Commission an electrical inspection before exchange of contracts.

Indicative costs

The figures below are indicative only and exclude VAT. They should be confirmed by written quotations from your chosen contractors.

Calder & Finch Surveyors is a trading name of Calder Finch LLP. Registered in England, number OC000000.

Item	Estimate
Chimney repointing	£450 to £650
Window sills (two)	£380 to £520
Roof tile repairs	£300 to £450
Gutter re-sealing	£120 to £180
Electrical inspection	£250 to £350
Total range	**£1,500 to £2,150**

We would be pleased to discuss any of these points with you. Please telephone me on 01234 000111 if you would like to arrange a meeting.

Yours sincerely,

Helen Calder MRICS
Senior Surveyor

Enc. Survey report (24 pages)